

DIRECTORS: VISCOUNT GOSCHEN, P.C., G.C.S.I., G.C.I.E., C.B.E., Sir BERNARD E. GREENWELL, Bart., JOHN CROSS, A. W. BOLDEN,
P. A. SANDERS, O.B.E., A.M.I. MECH. E., } Managing
E. P. PAXMAN, M.A.

DAVEY, PAXMAN & CO. (COLCHESTER) Ltd.,

Engineers and Boilermakers,

COLCHESTER.

Telegrams: "PAXMAN." COLCHESTER.

Telephone: 3151 & 3152 COLCHESTER.

COPY FOR LLOYDS.



ORDER No. 33/887 - 963.

TO BE QUOTED ON ADVICE AND INVOICE.

Messrs. Baldwins Limited,
P. O. Box, 286,
Shell-Mex House,
Strand,
London, W.C. 2

Date 24th June 1937.

PLEASE SUPPLY the undermentioned goods for our Account, and deliver free to

PRICE _____

TERMS OF PAYMENT _____

QUALITY.—The goods to be to our satisfaction, and _____

DELIVERY to be made _____

FORWARDING INSTRUCTIONS _____

One fuel service Tank of welded mild steel 2'0" dia. x 3'10" high made of 1/8" plate body and 3/16" plate ends, with handhole on top complete with cover and joint ring. Also pads welded on and tapped. Two bent plate supports welded on top and two shaped wash plates welded inside. Two 3" x 1 1/2" channels welded on bottom for fixing to drop tray but no drip tray to be supplied.

To be galvanised after manufacture and fitted with Simms 3" side geared magnetic level gauge. 1" galvanised drain plug to be supplied. All as per Drg. OHS/2569.
To be tested to 7 lbs. per sq. inch hydraulic pressure.

To be made of British material and to Lloyds and B.O.T. requirements and to be surveyed by Lloyds and B.O.T. to whom we are paying an inclusive fee.
Please work to the enclosed print.

Yours faithfully,

For and on behalf of
DAVEY, PAXMAN & Co. (Colchester) Limited.



© 2020

Lloyd's Register
Foundation