

COPY.

*L. O. ...  
...  
...  
...*

# Lloyd's Register of Shipping.

S.S. "DON RICARDO"



*This cert was sent by airmail*

Port TALCAHUANO, Chile, S.A.

May 26th., 1944.

## This is to Certify that

J. E. ALFARO H.,

the undersigned Surveyor to this Society did at the request of Messrs. Gibbs & Co., Lloyd's Agents and Owners, proceed to Lota, Caleta Chambeque on the 9th., inst. and following dates, in company of Mr. Ralph, Manager of Lloyd's Agents at Concepcion, for the purpose of examining damages sustained by the above named vessel which drifted ashore on Chambeque rocks and found that she was lying flat on solid rocks midship, in an extension of about 40 feet. Bottom and double bottom plates were found to be buckled up in way of transversal Bunker and Boiler Rooms.- Bulkheads in that part badly bent and broken at the base of them, as well as pillars, etc.; water was flooding in abundantly, invading Boiler and Engine Rooms, transversal Bunker and N°2 Hold.- Ships pumps could not be put in action.- Bow and Poop were floating, menacing ship to be broken into two parts.

In observing next day, at High and Low Tide, ship was found not to move, owing to the weight of water inside her. Cracks and bidges in Hull and Decks indicate probability vessel will break in half.- Diver could not penetrate under ship to look for damages owing to her position and tug boats or other vessels could not get alongside for pumping or helping on account of there being not sufficient depth and waves breaking roughly around.

Later on, after all kind of measures had been taken and seeing that ship was broken practically in two and there being not hope whatever of refloating her, all that could be done was to salvage and take ashore all movable gear as Capstan, windlasses, boats, booms, wireless, etc., etc., proceeding to make a complete list of them.

*J. E. Alfaro H.*

J. E. ALFARO H.  
INSPECTOR DE CONSTRUCCIONES  
NAVALES Y DE MAQUINAS DEL  
LLOYD'S REGISTER OF SHIPPING  
CABILLA 240  
TALCAHUANO (CHILE)

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."