

190 MAY 1943

ived by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME "DORYSSA" REPORT P.Nl. No. 3960

remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report. 24/5/92.)

The 1st S.S. No.1 due 8.42.

Permanent repairs are required to set in and holed shell plating at bottom of F.P. tank (p.s.) and to buckled and holed bottom in way of fore deep oil fuel tank at the first opportunity.

Action had been deferred pending further examination in dry dock and repairs.

The PORT NATAL Surveyor reports (2.43) the vessel placed in dry dock, ~~bottom coated.~~

On account of grounding, as above, keel plate No.1 holed and No.2 buckled, <sup>structure in way</sup> shell plating A.1 & 2 and B.1 holed, B.2 & 3 and C.2 indented, and bilge keel distorted (p.s.).

This damage was not examined internally as the spaces in way had previously been partly filled with cement which was not disturbed.

On account of lack of time temporary repairs have been effected by fitting welded foundation angles to the shell plates where badly indented and holed and cover plates fitted.

Permanent repairs are recommended at the first convenient opportunity. (1)

On account of damage through heavy weather, some deck fittings repaired and No.2 wing tank suction valves, s.s. spindles repaired.

On account of collision repairs effected to fore-castle bulkhead, bulwarks, guard rails, boats davits and upper and lower bridge structure.

The Surveyor recommends that a bower anchor be placed on board at the end of the present emergency. (2)

It is submitted the vessel appears worthy to remain as classed with record of docking survey 2.43 subject as recommended (1) and (2) but without other conditions.

As now, ) subject etc.  
2.43 P.Nl. ) without etc.



© 2019

6.5.43

Lloyd's Register  
Foundation

W241-0143