

Messrs. Chantiers de Normandie.

Trawler T8.

The Builders have forwarded plans of the main switchboard showing fuses mounted on the back of the board. This is contrary to Section 3, Clause 2(e), but has been accepted in previous cases provided there is ample clear space behind the board.


IT IS SUBMITTED the Le Havre Surveyors be informed the arrangement showing fuses mounted on the back of the switchboard ^{does not comply with Section 3 Clause 2 (e) but} might be accepted as in previous cases provided the space between the switchboard and the bulkhead be kept clear of obstruction so that the fuses are easily accessible. The minimum width of gangway behind the switchboard is to be not less than 600 mm.

In other respects the plans merit approval provided the installation be as shown and amended on the plans and the remaining requirements of the Rules for Electrical Equipment be complied with.

Return plan.
Retain copy.

R. F. L.

10th November, 1936.



Lloyd's Register
Foundation

W243-0097

[Handwritten signature]

[Handwritten signature]
L/11/36