

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

Enclosure.

30th June, 1936.

E.

Dear Sirs,

I duly received your letter of the 19th instant, forwarding plan, in triplicate, of shafting proposed by Messrs. Burmeister & Wain for a motor trawler "T 8" being built by Messrs. Chantiers de Penhoet at St. Nazaire, and with regard thereto I have to inform you that with 2 SCSA oil engines for driving auxiliary machinery, having 4 cylinders, 220 mm. diameter by 370 mm. stroke, span of bearings 277 mm., maximum pressure in cylinders 49 Kgs per sq. cm., M.I.P. 6.7 Kgs per sq. cm., B.H.P. 225, revolutions per minute 350, and crank arrangement as shown on the plan, the following sizes of crank shaft will be approved, viz:-

Journals.....150 mm. diameter.
Pins.....150 mm. diameter with a central hole
75 mm. diameter.

Two copies of the approved plan are returned herewith.

I am, Dear Sirs,
Yours faithfully,

The Surveyors,
COPENHAGEN.



Lloyd's Register
Secretary.
Foundation

W243-0133