

PUMPING ARRANGEMENT Endorsement.

Shipbuilders: Messrs. *Chantiers et Ateliers de*
St. Nazaire, Penhoët
Engineers: Messrs. *Steel Trawler*
Owners: Messrs.

Yard No. —

Engine No.

diagrammatic

It is submitted that the ^{diagrammatic} plan of
Pumping Arrangement *in the machinery space*
merits approval, provided the arrangements be as
shown and amended on the plan and the remaining
requirements of ~~Sections 20 and 34 of the Rules (19 —)~~ *the Rules for Steel Trawlers*
be complied with so far as they are applicable.

*It should be pointed out that power
pump suction should be fitted for
draining the forward store and the
deep cofferdam at frames 44-45, and
suitable provision made for the drainage
of the fore peak, pipe tunnel, and aft
cofferdam at frames 13-14.*

*Further, the discharges from the
auxiliary pumps to the hold spaces should
be dispensed with in order to ^{clause 6} comply with
the requirements of Section 25 of the Rules.*

*A plan of the oil fuel piping arrangement
should be submitted.*

Return plan.

Retain copy.

E. 4. 5c.236. T.



© 2020

J. McA
18/4/36

Lloyd's Register
Foundation

W243-0162