

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

Enclosure.

20th March, 1936.

Dear Sirs,

E. I was duly favoured with your letter of the 13th instant, forwarding a plan, in triplicate, showing details of shafting proposed for the engine being built by your goodselves for a Trawler intended for Mr. Huret, of Bordeaux, and with regard thereto I have to inform you that, with 4 SCSA oil engines for main propelling purposes, having 7 cylinders, diameter of cylinders 450 mm., stroke 850 mm., revolutions per minute 165-170, maximum pressure in cylinders 46 Kgs. per square cm., B.H.P. 1030, diameter of propeller 3000 mm. and screw shaft with continuous liner, the following sizes of shafting will be approved, viz:-

Thrust ..... 300 mm. dia. in way of collars  
and reduced to 282 mm. dia.  
Intermediate ... 242 mm. dia.  
Screw ..... 267 mm. dia.

The plan showing details of shafting will also be approved, and one copy is returned herewith.

I am, Dear Sirs,

Yours faithfully,

S.A. Chantier & Atelier de St. Nazaire,  
Chantier de Penhoet,  
SAINT NAZAIRE.

© 2019  
Lloyd's Register  
Secretary.  
Foundation

W243-0166