


Steamer "KUMANOVO"

It is submitted the Surveyor be informed that the Rules require the boundary angles of oil fuel bunkers to be double riveted (or alternatively double angles single riveted may be fitted) with the rivets in these angles spaced 5 diameters apart. No objection need be taken, however, to spacing these rivets 4 diameters apart, if specially desired.

Ltr. 19/11. Anal. 25/11


25.11.35



© 2019

Lloyd's Register
Foundation

W248-0170