

LOYD'S LIST & SHIPPING GAZETTE, TUES.

*Jan 5*  
**KINGSWOOD.**—Adelaide, Jan. 4.—  
 Donkey boiler of British steamer Kings-  
 wood, at Port Pirie anchorage, exploded  
 yesterday morning, being blown  
 through all forward starboard bulk-  
 heads and finally lodging in forepeak,  
 holing bow 30 ft. 1 ft. above water-  
 line. Main boilers set back 3 ft., main  
 engine 3 in., other extensive damages.  
 Tugs assisting to berth at Port Pirie  
 to-morrow.

*Jan 9.*  
**KINGSWOOD.**—Adelaide, Jan. 8.—  
 British steamer Kingswood: Lloyd's  
 Register Sydney Surveyor present.  
 Auxiliary boiler projected through for-  
 ward bulkheads, lodged forepeak, star-  
 board bow plating holed, involving six  
 shell plates and eleven frames. Bridge  
 superstructure damaged. Main boilers  
 forced back against engines, cylinder  
 feet broken, back columns broken, front  
 columns bent, high pressure piston rod  
 and connecting rod bent, all pipe work  
 in engine and boiler spaces, condenser,  
 main engine pumps, fan, engine feed  
 pumps, low pressure turbine badly  
 damaged, engine and boiler room full of  
 debris. To enable vessel to be towed  
 to port of repair, can effect temporary  
 repairs at Port Pirie to shell plating  
 frames and forward bulkhead. Necessary  
 instal donkey boiler temporarily for  
 pumping and steering, &c. Necessary  
 tow vessel to port of repair. Engine  
 and boilers badly damaged, will require  
 removal for permanent repairs. Lloyd's  
 Register Sydney Surveyor proposes pre-  
 paring specification, as full as possible,  
 for permanent repairs and invite tenders  
 Australia.—Lloyd's Agent per Salvage  
 Association.

W249-0255

Foundation