



- RIVETING.
- FRAMES WITH SHELL PLATING
 - DIAM. 22" in STRAKE "L" AND STRAKES BELOW.
 - 19" in ALL STRAKES ABOVE STRAKE "L"
 - SPACING FRAMES 7 AND ALL FRAMES FORWARD
 - BELOW "DECK F" 5 1/2 DIA. APART
 - ABOVE "DECK F" 7 DIA. APART
 - FRAME NO 8 (COLLISION BND. BOUND. F) 5 DIA. APART
 - FRAMES 9 AND MORE AFT.
 - DEEP FRAMES L 5 1/2 DIA. APART
 - BULB ANGLE FRAMES 7 DIA. APART
 - SEAMS. 4 DIA. APART.
 - BUTT LAP. DR. AND TR. 3 1/2 DIA. APART.
 - QR. 4 DIA. APART
 - DECK STRINGER ANGLES 4 1/2 DIA. APART

MERCANTILE MARINE ENGINEERING AND
DRAWING DOCK CO. S.A. 25-4-36

S.S. LEOPOLDVILLE.
MODIFICATION ON SHELL PLATING.

SCALE 1/50
PLAN 1904-15-A-1.