

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

Enclosure.

19th March, 1937.

Dear Sirs,

E.


The Burntisland S.B. Co's Yard No.218.
Messrs. Rankin & Blackmore's No.456.

I return herewith one copy of the plan, forwarded with your letter of the 11th instant, of Main Boilers proposed for the above vessel, and have to inform you that this plan will be approved for a working pressure of 200 lb. per square inch, provided nuts be fitted to two stay tubes at the front tube plate and the riveting of the manhole compensating plate be amended as shown on the plan, and the boilers be constructed under the usual conditions of survey and testing.

The Steel Testing Surveyors should be advised regarding the tensile strength of the shell plates, butt straps, manhole compensating plate and combustion chamber girder plates, viz:- 29-33 tons per square inch.

I am, Dear Sirs,
Yours faithfully,

The Surveyors,
GREENOCK.



Lloyd's Register
Foundation

2110-9520