

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

25th May, 1937.

Dear Sirs,


E. I duly received your letter of the 10th instant, forwarding a plan, in duplicate, of air receiver proposed for Messrs. L. Smit & Zoon's Yard No.889.

With regard thereto I have to inform you that this plan of air receiver having a water gas welded longitudinal seam will be approved for a working pressure of 30 Kgs. per sq. cm., provided satisfactory results be obtained from two tensile and two bend tests carried out on specimens taken in the way of the longitudinal joint, for which purposes the shell plates should be made long enough to provide test pieces, and, further, provided the circumferential seams be double riveted as required by the Rules instead of single riveted as proposed, and the receivers be constructed under the usual conditions of survey and testing.

One copy of the plan is being returned to you under separate cover.

I am, Dear Sirs,
Yours faithfully,

The Surveyors,
ROTTERDAM.



Lloyd's Register
Foundation

W258-0091