

69462.

The Scottish Tube Co. Ltd.,
Govan Tube Works,
Helen Street,
G O V A N.

17th. Jany. 1919.

SPECIFICATION of Lapwelded Wrot. Iron Main Steam Pipes

For Caird & Co. Ltd., G R E E N O C K.

Order 12/8/18.

Contract No. 482.

- 6 - Bent Pipes made from $5\frac{1}{2}$ " O.D. x $5/16$ " thick, sorewed at ends with vanishing threads and fitted with Flanges to diameters and thicknesses as specified, screwed on, faced plain, turned on edge and having tube ends expanded into Flanges.

All Pipes annealed.

Working Pressure

180 Lbs. per Square inch.

Test Pressure

540 Lbs. per Square inch.

All to LLOYD's Requirements.



© 2021

Lloyd's Register
Foundation

W26 - 0098