

Vessels building by Messrs. J.L. Thompson & Sons, Ltd.

It is submitted the Sunderland Surveyors be informed that if it is desired to omit the girders from the rudders in these vessels, the thickness of the side plating in Nos. 589, 590 & 591 should be .66" and in No. 588 .70", provided the plating is riveted to the rudder arms.

If it is desired to retain the present system of construction by attaching the plating to the arms by slot welds, it is considered that the web plates at present shewn on the plans should be retained.

WJ

WJ

30. 5. 38.

Ltr. 25. 5. 38.
Asd. 30. 5. 38.



© 2019

Lloyd's Register
Foundation

W261-0264