

s.s. "SILVERLAUREL".

Messrs. J.L. Thompson & Sons' Yard No. 588.

Refrigerating Installation.

IT IS SUBMITTED Messrs. Gregson & Co. Ltd. be informed that the plans and specification of the proposed insulation merit approval provided the fastenings of the insulation be to the Surveyors' satisfaction, the arrangements be as shown and amended and the remaining requirements of the Rules for Refrigerating Machinery and Appliances be complied with so far as they are applicable.

In connection with the amendments shown on the plans and specification, it might be pointed out that the proposed single wood linings adjoining the general cargo spaces are not considered to be proof against the contamination of refrigerated cargoes by odorous goods which may be carried in these spaces, and that these linings should be double with waterproof paper between. Further, that the woodwork should be carefully fitted and jointed to the deck plating and overheading.

IT IS FURTHER SUBMITTED the Sunderland Surveyors be fully advised and furnished with copies of the amended plans and specification. They should be asked to forward to this Office plans showing the proposed draining arrangements and type of scuppers in the refrigerated spaces.

Return Plans and Specification to Messrs. Gregson & Co. Ltd.
Forward Copies of Plans and Specification to Sunderland Surveyors.
Retain copies.

Lo 25/1

W261-0308

© 2019
Lloyd's Register
Foundation
24th January, 1939.