


(LLOYDS REGISTER.)

G. R. 130
Lloyds Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.
Letters (if any) *J. T. F. S.*



Official Number. <i>2,256</i>	Name of Ship. <i>Wellpark</i>	No., Date, and Port of Registry. <i>2/1918, Greenock</i>
----------------------------------	----------------------------------	---

Date, and Port of Previous Registry (if any). *New Vessel.*

Whether British or Foreign Built. <i>British</i>	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled. <i>Steamship Single screw</i>	Where Built. <i>Grangemouth</i>	When Built. <i>1918</i>	Name and Address of Builders. <i>The Greenock Dockyard Co. Ltd Grangemouth.</i>
Number of Decks ...	<i>One</i>	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet. <i>280</i>	Tenths. <i>0.</i>
Number of Masts ...	<i>Two</i>	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	<i>279</i>	<i>8.</i>
Keel ...	<i>Schooner elliptical</i>	Main breadth to outside of plank ...	<i>41</i>	<i>9.5</i>
Rigging ...	<i>Clincher</i>	Depth in hold from tonnage deck to ceiling at midships ...	<i>18</i>	<i>9</i>
Deck ...	<i>None</i>	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...		
Material of hull ...	<i>Steel</i>	Depth from top of beam amidships to top of keel ...	<i>22</i>	<i>0.</i>
Number of Bulkheads ...	<i>cargo</i>	Depth from top of deck at side amidships to bottom of keel ...	<i>20</i>	<i>9.5</i>
Number of water ballast tanks, and their capacity in tons ...	<i>Four six 674 Tons.</i>	Round of beam ...	<i>1</i>	<i>2</i>
		Length of engine room, if any ...	<i>50</i>	<i>0.</i>

PARTICULARS OF DISPLACEMENT.

At quarter the depth from weather deck at side amidships to bottom of keel ... *4090* Tons. Ditto per inch immersion at same depth ... *23.3* Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
				No. and Diameter of Cylinders in each set.	Length of Stroke.		
<i>Inverted direct acting triple expansion condensing</i>	<i>British</i>	<i>1918</i>	<i>Dunsmuir & Jackson Glasgow.</i>	<i>Three</i>	<i>36"</i>	<i>-</i>	<i>230 1000 10 knots</i>
Particulars of Boilers.							
<i>Cylindrical multitubular</i>	<i>British</i>	<i>1918</i>					
Number ...							
Iron or Steel ...							
Loaded Pressure ...							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	<i>1792.31</i>	On account of space required for propelling power	<i>682.87</i>
Space or spaces between Decks ...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	<i>75.23</i>
Turret or Trunk ...		These spaces are the following, viz.:—	
Forecastle ...	<i>44.97</i>		
Bridge space ...	<i>136.26</i>		
Poop or Break ...	<i>47.42</i>		
Side Houses ...	<i>23.11</i>		
Deck Houses ...	<i>38.33</i>		
Chart House ...	<i>6.65</i>		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways ...	<i>44.91</i>	Machinery Accommodation ... <i>5.59</i>	
Gross Tonnage ...	<i>2133.96</i>	Boatswain's Stowage ... <i>18.40</i>	
Deductions, as per Contra ...	<i>823.87</i>	Wireless Telegraphy Space ... <i>3.26</i>	
Registered Tonnage ...	<i>1310.09</i>	Chart Space ... <i>6.65</i>	
		Water Ballast Spaces ... <i>31.87</i>	
		Total ...	<i>65.77</i>
			<i>823.87</i>

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is *309.84* tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is *86.49* tons.
NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Name of Master *Edward Jones* Certificate of { Service No. *014174*
Competency No. *014174*

No. of Owners
Name, Residence, and Description of Managing Owner if there are more owners than one. *John Denholm, of Sugar Exchange, Greenock.*

Dated *27th April 1918* *Sixty-four shares.*
Lloyd's Register
TUE. JUN. 22 1920
FRI. 28 MAR. 1919
TUE. 30 MAY 1922

5010-3923

