

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.


15th February, 1938.

Dear Sirs,

E. I duly received your letter of the 2nd instant, with plan in triplicate of donkey boiler proposed by Messrs. Christiansen & Meyer for Messrs. Schichau's Yard No.1424, and I have to inform you that this plan, as shown and amended, will be approved for a working pressure of 7 kg. per sq. cm., provided the pitch of the rivets in the circumferential seams be not less than 60 mm, the thickness of the dished furnace crown plate be not less than 22 mm, or alternatively, the external radius of the dished furnace crown plate be not greater than 1450 mm, the thickness of the cross tubes be not less than 9.5 mm, the welded attachment of the cross tubes in way of the firehole be as indicated on the plan, the welding be to your satisfaction and the boiler be constructed under the usual conditions of survey and testing.

It is noted the tensile strengths of the material will be similar to those shown on plan No.6080 approved in my letter of the 1st November, 1937, for Messrs. Shichau's Yard No.1419.

Two copies of the plan are being returned



© 2019

Lloyd's Register
Foundation

W264-0065

COPY.

Messrs. Schichau's Yard
No. 1424.

to your address today, under separate cover.

I am, Dear Sirs,

Yours faithfully,

Secretary.

The Surveyors,
HAMBURG.



© 2019

Lloyd's Register
Foundation

2/2 W264-0065