

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

Enclosures.

Ref:- AM.Wgd/M.

24th March, 1938.

Dear Sirs,

Yard No. 1424 - "OSLO IV".

E.

I beg to acknowledge the receipt of your letter of the 18th instant, forwarding plans, in duplicate, of shafting proposed in connection with the above vessel.

The plans have been examined and I have to acquaint you that with 2 SCSA oil engines for main propelling purposes, having 9 cylinders, diameter 650 mm., stroke 1200 mm., M.I.P. 5.904 Kgs per sq. cm., diameter of propeller 4800 mm., and screw shaft with continuous liner, the following sizes of shafting will be approved, viz:-

Intermediate..... 365 mm. diameter.
Screw..... 436 mm. diameter.

The plans showing details of shafting and loose coupling will also be approved, and one set of these plans is returned herewith.

I shall be obliged if you will kindly furnish me with particulars of the B.H.P. and revolutions per minute of this Engine for purposes of reference in this Office.

Messrs. F. Schichau, G.m.b.H.,

ELBING.

I am, Dear Sirs,
Yours faithfully,

Lloyd's Register
Foundation

Secretary.

W264-0121