

Messrs. Schichau No. 1424

It is submitted the Builders be informed that having in view the thickness of the rider plates forming the bottom of the girders the doubling plates proposed by them to be fitted on the heads of the tween deck tubular pillars may be omitted. Special care should be taken should be taken to ensure that the pillars have a bearing fit on the rider plates. It is considered, however, that the usual doubling plates should be fitted on the heads of the hold pillars.

JRL
24.9.38.

for Mr Parts

Ltr. 15. 9. 38.
Asd. 24. 9. 38.
2 plans 1 retained.
P.C. Danzig.



© 2019

Lloyd's Register
Foundation

W264-0144