


Messrs. F. Schichau's Yard No. 1357.


It is submitted the Builders be informed that the proposal to supply three stockless bower anchors of 4,400 Kgs. each is in order.

If desired 550 metres of $2\frac{1}{4}$ " diameter "Tayco" cable, tested in accordance with the Committee's practice for this type of cable, will be accepted, in lieu of 550 metres of 2.10/16" diameter ordinary cable shewn on the plan of midship section.

The proposal to use seamless tubes of material having a tensile strength of 55-⁶⁵~~56~~ Kg./sq.mm. and an elongation of 14% for pillars of less than 300 m/m diameter, and to reduce the thicknesses shewn on the approved plan by 25% will be approved, provided the thicknesses so reduced be not less than 1/30th of the diameter.

*Dr. 20/12/35
Approved
P.C. Sdy.*


24. 12. 35.



© 2019

Lloyd's Register
Foundation

W264-0306