

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

3rd July, 1939.

Dear Sirs,

E.
I am returning to you under separate cover one copy of the plan, advised in your letter of the 19th ultimo, of Steam Piping Arrangement proposed for Messrs. Wilton-Fyenoord's Yard No.669, and have to inform you that this plan will be approved for a working pressure of 14 kgs. per sq. cm., provided the steel steam pipes of 40 mm. nominal bore be solid drawn cold finished, or, alternatively, if of solid drawn hot finished pipe, be not less than 3.75 mm. thick, all pipes and fittings subjected to steam temperature exceeding 425°F. be of steel, the drainage arrangements be to your satisfaction, all steel castings be made at approved Works and tested as required by the Rules, and the whole of the work be carried out under the usual conditions of survey and testing.

I am, Dear Sirs,

Yours faithfully,

The Surveyors,
ROTTERDAM.



© 2019

Secretary,
Lloyd's Register
Foundation

W290-0036