

S.S. "HELLESUND".

No. 75851 in The Register Book.

Boilermakers: A.S. Glommens Mek. Verkstad, Fredrikstad
for Messrs. G.G. Amundsen A/S Oslo.

The Oslo Surveyors forward for consideration the plan of a donkey boiler, the material of which has been tested by the Germanischer Lloyd Surveyors and was originally intended for an unclassed vessel.


The Surveyors request to be informed if the material could be accepted for use in constructing a donkey boiler for the above named vessel - classed with this Society.

The scantlings of the boiler as shown on the plan are in excess of those required by the Rules for the intended working pressure.

The results of the tests of the materials as shown on the Germanischer Lloyd certificate are satisfactory.

IT IS SUBMITTED the Oslo Surveyors be informed that the scantlings of the boiler as shown on the plan merit approval for a working pressure of 7 kg. per sq. cm. provided that on completion of the welding of the fittings and manhole compensating plate, and before rivetting is commenced, the cylindrical shell of the boiler be efficiently heat treated. It is noted that the material for the construction of this boiler has been tested by the Surveyors to the Germanischer Lloyd and the results of the tests as shown on the certificate are considered satisfactory. The material in question could be accepted provided the same be examined and be found satisfactory and check tests carried out on portions cut from the material confirm the results shown on the test certificates.

2 plans and certificates
1 copy of plan. Lr 13/6



© 2019
Lloyd Register
Foundation

W295-0153