

Messrs. Philip & Son's Yard No. 847.

It is submitted the Builders be informed in reply to their enquiry that the note on the plan No.10673 S. shewing details of fresh water ballast and oil fuel tanks refers to Section 27, Clause 2(d) of the Rules for Steel Yachts, wherein it is required that brackets be fitted to the ends of stiffeners on bulkheads forming the boundaries of deep tanks. In the present case brackets should be fitted to all stiffeners on the following transverse bulkheads Nos. 44, 49, 51, 55, 58 & 62.

[Signature] *[Signature]*
31. 8. 37.

Rev. 30/8. Ansd. 31/8
1 plan n.c. Ply.



© 2019

Lloyd's Register
Foundation

W307-0116