

ESTABLISHED 1858.

C CONTRACTORS TO THE
ADMIRALTY, WAR OFFICE, CROWN AGENTS FOR COLONIES
AND FOREIGN GOVERNMENTS.

TELEGRAPHIC ADDRESS:
PHILIP DARTMOUTH
TELEPHONE NO 12 DARTMOUTH.

JET/DP.

LONDON OFFICE:- BALTIC HOUSE, LEADENHALL ST., E.C.3.
PHONE:- MONUMENT 2161.

MAKERS OF ALL CLASSES OF WATER TUBE BOILERS.

INCLUDING LUNE VALLEY FLASH BOILERS AND BURNERS.

PHILIP & SON, LIMITED,

(INCORPORATING THE BUSINESS OF
SIMPSON, STRICKLAND & CO LTD)

SHIPBUILDERS AND ENGINEERS.

FLOATING DOCK PROPRIETORS.

SOLE AUTHORISED DEALERS IN
DEVON FOR MORRIS MARINE AND
INDUSTRIAL ENGINES.

*Sandquay & Noss Engineering Works,
Dartmouth.*

12th August, 1937.

9 plan
The Secretary,
Lloyds Register of Shipping,
71, Fenchurch Street,
London. E. C. 3.

Dear Sir,

New Twin Screw Motor Yacht No. 847.

We beg to refer to your letter of the 4th inst. and to the drawing of the General Steel Work in particular.

In dealing with this plan you indicated that the side frames in way of the windows in the deck saloon should extend up through the main deck and terminate at carlings introduced below the window openings. This is not practicable as these windows are of the vertical sliding type, the operating gear of which extends down to within a few inches of the deck.

We have discussed the matter with Mr. Norman Hart, and if it is definitely considered that additional strength here is desirable, we have agreed that in lieu of extending the frames and subject to your approval, we increase the side plating from 6/20" to 7/20" thick in way of these windows. The frame angles

W307-0123 1/2

Lloyds Register of Shipping.

No. 2.

between the windows together with the reverse frames to extend right up as indicated.

We trust you are agreeable to this.

We also submit herewith the following plans in triplicate for your approval, viz:-

10669.S. Stern frame and rudder.


10663.S. Fresh water tank abaft of engine room.

10673.S. Fuel tanks, fresh water tank and ballast tank forward of engine room.

All these plans have been specially agreed with Mr. Hart and we shall be glad of your approval as soon as possible.

Yours faithfully,

FOR PHILIP & SON, LIMITED.


.....Secretary.

enc.

AS



© 2019

Lloyd's Register
Foundation

W307-0123 2/2

Referred to the Chief Ship Surveyor.

H/B

13 AUG 1937

Req early reply

•The vessel's name?



© 2019 Lloyd's Register Foundation