

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) G.W.P.T.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
163,446.	Arctees.	20 in 1934 London.

No., Date, and Port of Previous Registry (if any). ---

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship: Single Screw.	Haverton Hill on Tees.	1934	Furness Shipbuilding Company Limited Haverton Hill.
Number of Decks ..	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ..	362	Feet. 5
Number of Masts ..	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ..	359	7
Rigged ..	Schooner	Main breadth to outside of plank ..	57	5
Stern ..	Cruiser	Depth in hold from tonnage deck to ceiling at midships ..	23	6.5
Build ..	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ..	--	--
Galleries ..	None	Depth from top of beam amidships to top of keel ..	25	7.5
Head ..	None	Depth from top of deck at side amidships to bottom of keel ..	25	9.28
Framework and description of vessel ..	Steel Cargo	Round of beam ..	1	1
Number of Bulkheads ..	Six	Length of engine room, if any ..	44	3.5
Number of water ballast tanks, and their capacity in tons ..	Seven 903 tons.			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel. 7765 Tons. Ditto per inch immersion at same depth 39.9 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Speed of Ship.
One	Direct Acting Surface Condensing Triple Expansion.	British	1934	North Eastern Marine Engineering Co., Ltd., Wallsend.	Three 21"	42"	----	357
One	Cylindrical Multitubular	British	1934		37"	62"		1750
	Number Three							
	Iron or Steel Steel							
	Loaded Pressure 220 lbs.							
								11 1/2 knots

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ..	3666.15	On account of space required for propelling power	1264.89
Space or spaces between Decks ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	197.38
Turret or Trunk ..		These spaces are the following, viz. :-	
Forecastle Houses in	7.14	In Poop, Round Houses.	
Bridge space --do--	11.27	(Number of Seamen or Apprentices for whom accommodation is certified.. 37.....)	
Poop or Break ..	75.51	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-	
Side Houses ..		Master's Accommodation 13.72)	
Deck Houses Round	153.83	Chart Space 5.37)	
Chart House ..	5.37	Wireless Space 3.08)	108.94
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ..	15.41	Boatswain's Store 18.81)	
Excess of Hatchways ..	18.09	Water Ballast Space 67.96)	
		Total ..	1571.21
Gross Tonnage ..	3952.77		
Deductions, as per Contra ..	1571.21		
Register Tonnage ..	2381.56		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 500.71 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 123.13 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle	L. 30.6'	- 45.19 tons.
Bridge	L. 226.3'	- 804.56 "
Open Space F.E. Bridge	L. 2.3'	- 8.97 "
" " A.E. Bridge	L. 2.3'	- 8.81 "

Name of Master

Certificate of

{ Service
CompetencyNo.
No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

Arctees Shipping Company Limited
4, Lloyds Avenue,
London.
Shares:- Sixty-four.

Sir Joseph William Isherwood Bt.
of same address-Manager-

Dated 27th February 1934.

26. Wt. 11709/390. 2,000. 9/32. Wy.P.C. Gp. 613.

W31-0062