

COPY.  
COPY.

20 FEB 1934

7107

From STEWARTS and LLOYDS LIMITED, COATBRIDGE.

To

1.42/703.

Messrs. Furness Shipbuilding Co. Ltd.,  
Haverton Hill Shipyard,  
Haverton Hill-on-Tees.

Order No. 226/32 of 5/7/33.

No. 226 Ship.

Mark:- 226.

Derricks built up of Steel Tubes in  
sections of dimensions as detailed,  
crossed and shrunk together at joints  
when hot.

Extreme ends reduced as shewn.

6 Derricks x 43ft.  $3\frac{1}{2}$ " long,  
each comprising:-

1 - 9 $\frac{1}{2}$ " o.d. x 13ft.3" x 5/16" thk. Teles.18"

1 - 10 $\frac{1}{2}$ " o.d. x 22ft.1" x 5/16" thk.

1 - 9 $\frac{1}{2}$ " o.d. x 10ft.11 $\frac{1}{2}$ " x 5/16" thk. Teles.18"  
Item Nos.1,2 & 5.

2 Derricks x 43ft.  $3\frac{1}{2}$ " long,  
each comprising:-

1 - 9 $\frac{1}{2}$ " o.d. x 13ft.3" x 5/16" thk. Teles. 18"

1 - 10 $\frac{1}{2}$ " o.d. x 22ft.1" x 5/16" thk.

1 - 9 $\frac{1}{2}$ " o.d. x 10ft.11 $\frac{1}{2}$ " x 5/16" thk. Teles.18"  
Item No. 4.

For 5 Ton Loads.

Test to 275 lbs. per sq. in.

2 Derricks x 36ft.2 $\frac{1}{2}$ "  
each comprising:-

1 - 8 $\frac{1}{2}$ " o.d. x 11ft.0" x 1/4" thk. Teles.18"

1 - 9 $\frac{1}{2}$ " o.d. x 19ft.3" x 1/4" thk.

1 - 8 $\frac{1}{2}$ " o.d. x 8ft.11 $\frac{1}{2}$ " x 1/4" thk. Teles.18"

Item No.3.

For 3 Ton Load.

© 2020 Rkm acmillan

Lloyd's Register  
Foundation

W31-0070(12)



COPY.

20 FEB 1934

c 7157

From STEWARTS and LLOYDS LIMITED, COATBRIDGE.

To

I.42/703.

2

Messrs. Furness Shipbuilding Co. Lt

Derricks open at both ends and without  
fittings of any kind.

To custrs. drawing.

Inspected and tested to the satisfaction of  
Lloyds and Certificates supplied free,  
also subject to the Owners and Customers  
complete satisfaction.

*RKmacmillan*



© 2020

Lloyd's Register  
Foundation