

Rpt. 13.

No. 45491

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Date of writing Report 24.7.1926 When handed in at Local Office 16.8.1926 Port of GLASGOW. Received at London Office 18 AUG 1926

No. in Survey held at GLASGOW. Date, First Survey 1st June Last Survey 14th June 1926
Y. Reg. Book. 3870 on the M. Y. "MINGARY" (Number of Visits... 5)Tons { Gross 223
NetBuilt at GLASGOW. By whom built ALEX^R. STEPHENSON & SON Ward No. 511 When built 1926.

Owners KENNETH. M. CLARK ESQ. Port belonging to GLASGOW.

Electric Light Installation fitted by MESSRS J. H. HOLMES & CO Contract No. 511 When fitted 1926.

System of Distribution Double Wire System.
Pressure of supply for Lighting 110 volts, Heating 110 volts, Power 110 volts.

Direct or Alternating Current, Lighting Direct Power Direct

If alternating current system, state frequency of periods per second -

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes.

Generators, do they comply with the requirements regarding overload Yes, are they compound wound Yes.

are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator -

Where more than one generator is fitted are they arranged to run in parallel - is an adjustable regulating resistance fitted in series with each shunt field Yes.

Are all terminals accessible and clearly marked Yes, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited Yes.

Are the lubricating arrangements of the generators as per Rule Yes.

Position of Generators Fore End, centre of Engine Room.

is the ventilation in way of the generators satisfactory Yes, are they clear of all inflammable material Yes.

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators - and - are the generators protected from mechanical injury and damage from water, steam or oil Yes.

are their axis of rotation fore and aft Yes.

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes, are the prime movers and their respective generators in metallic contact Yes.

Main Switch Boards, where placed Aft End, centre of Engine Room.

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard -

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes.

are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards - and -

are they constructed wholly of durable, incombustible non-absorbent materials Yes, is all insulation of high dielectric strength and of permanently high insulation resistance Yes.

if semi-insulating material is used, are all conducting parts connected to one pole insulated from the slab with mica or micanite and the slab similarly insulated from its framework Yes, and is the frame effectively earthed Yes.

Are the following fittings as per Rule, viz.:— spacing or shielding of live parts Yes, accessibility of all parts Yes, absence of fuses on back of board Yes, proportion of omnibus bars Yes.

individual fuses to voltmeter, pilot or earth lamp Yes, connections of switches Yes.

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Double Pole knife switch + single Pole fuses on dynamo mains. Single Pole changeover knife switches + single Pole fuses on each outgoing circuit.


Instruments on main switchboard 3 ammeters 2 voltmeters - synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Earth lamps coupled to earth through fuses switches.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes.

Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes.



© 2019

Lloyd's Register
Foundation

W315-0059(112)

Insulation of Cables, state type of cables, single or twin *Single* are the cables insulated and protected as per Tables III or IV of the Rules *Yes*.

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load *3.5 volts*.

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets *Yes*.

Paper Insulated Cables, If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *None*.

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *Yes*.

Support and Protection of Cables, state how the cables are supported and protected *Main cables, but main cables to motor all lead covered & armoured clipped up with lead. Iron clips. Branch wiring to lights in engine room & Accommodation, V.H.R. in enamelled soaped steel conduits.*

If cables are run in wood casings, are the casings and caps secured by screws *—*, are the cap screws of brass *—*, are the cables run in separate grooves *—*. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VI *Yes*.

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements *None fitted*.

Joints in Cables, state if any, and how made, insulated, and protected *None, looping in system fitted*.

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *Yes*.

Bushes in Beams and Non-watertight Positions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *Yes*. state the material of which the bushes are made *fibre*.

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *—*.

are their connections made as per Rule *—*.

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *Yes*.

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven *None*.

Navigation Lamps, are these separately wired *Yes*, controlled by separate switch and separate fuses *Yes*.

are the fuses double pole *Yes*, are the switches and fuses grouped in a position accessible only to the officers on watch *Yes*.

has each navigation lamp an automatic indicator as per Rule *Yes*, are separate screens provided for the use of oil and electric side lights *Yes*.

are separate oil lanterns provided for the mast head lights and side lights *Yes*.

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *Yes*.

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *No*.

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *No*.

how are the cables led *—*.

where are the controlling switches situated *—*.

Searchlight Lamps, No. of *1*, whether fixed or portable *portable*, are their fittings as per Rule *Yes*.

Arc Lamps, other than searchlight lamps, No. of *—*, are their live parts insulated from the frame or case *—*, are their fittings as per Rule *—*.

Motors, are their working parts readily accessible *Yes*, are the coils self-contained and readily removable for replacement *Yes*.

are the brushes, brush holders, terminals and lubricating arrangements as per Rule *Yes*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *Yes*.

are they protected from mechanical injury and damage from water, steam or oil *Yes*, are their axis of rotation fore and aft *Yes*.

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *Yes*.

totally enclosed, if not of this type, state distance of the combustible material horizontally or vertically above the motors *—* and *—*.

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed as per Rule *Yes*.

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule *—*.

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *—*.

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *—*.

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN ...	1	7.5	110	68.75	550	Gardner oil engine	Diesel oil	180°
AUXILIARY ...								
EMERGENCY ...								
ROTARY TRANSFORMER								

LIGHTING AND HEATING CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR...	2	.0600	19	.064	68	128	U.S.R.	Lead Covered & Armoured.
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER...								
	AUXILIARY SWITCHBOARDS								
	ENGINE ROOM	2	.00299	3	.036	2.7	40	U.S.R.	Lead Covered & Armoured.
	Boiler Room								
	Saloon & Navigation	2	.01462	4	.052	11.0	180	"	" " " "
	Cabin Room & Forward	2	.01046	4	.044	7.5	160	"	" " " "
	State Room & Living Room	2	.01046	4	.044	9.5	90	"	" " " "
	Wireless								
	1 SEARCHLIGHT (portable)	2	.00194	3	.029	.7	24	U.S.R.	In Enamelled Conduit.
	1 MASTHEAD LIGHT	2	.00194	3	.029	.9	162	"	" Galv. " "
	2 SIDE LIGHTS each	2	.00194	3	.029	.9	50	"	" " " "
	2 COMPASS LIGHTS each	2	.00194	3	.029	.09	75	"	" Enamelled " "
	Boat Lights								
	Cargo Lights								
	Arc Lamps								
	2 HEATERS each	2	.00455	7	.029	.9	75	U.S.R.	In Enamelled Tubing

MOTOR CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	Engine Room BILGE PUMP	2	.01462	4	.052	18.6	80	U.S.R.	Lead Covered & Armoured.
	SANITARY PUMP								
	SEA WATER PUMPS	2	.00194	3	.029	2.6	60	"	" " " "
	FRESH WATER PUMPS	2	.00299	3	.036	2.6	80	"	" " " "
	AIR COMPRESSOR	2	.02960	19	.052	43.2	90	"	" " " "
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP	2	.00299	3	.036	4.8	56	U.S.R.	Lead Covered & Armoured.
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	WORKSHOP MOTOR								
	VENTILATING FANS								
	Capstan Motor	2	.02960	19	.052	43.2	204	"	" " " "
	Fire Pump	2	.01462	4	.052	18.6	10	"	" " " "
	Hot Water Pump	2	.00299	3	.036	2.6	60	"	" " " "
	Refrigerating Motor	2	.00194	3	.029	2.6	160	"	" " " "

All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

J. H. Holmes & Co. Electrical Engineers.

Date *10/8/26*

COMPASSES.

Distance between electric generators ~~or motors~~ and standard compass *35 ft approx.*

Distance between electric generators or motors and steering compass *no steering compass fitted*

The nearest cables to the compasses are as follows:—

A cable carrying *approx 0.9* Amperes *inside* feet from standard compass feet from steering compass.

A cable carrying " *3.6* Amperes *approx 20* feet from standard compass feet from steering compass.

A cable carrying " *6* Amperes " *8* feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power. *Yes.*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted. *Yes*

The maximum deviation due to electric currents was found to be *no* degrees on *any* course in the case of the standard compass, and — degrees on — course in the case of the steering compass.

ALEXANDER STEPHEN & SONS, LIMITED.

Shirley B. Balston Director.

Builder's Signature.

Date *13 Aug 1926*

Is this installation a duplicate of a previous case *no* If so, state name of vessel —

General Remarks (State quality of workmanship, opinions as to class, &c.)

*One battery of 60 Donlad cells fitted in 4 trays in Engine Room.
Capacity 148 ampere hours @ 10 hour rate of discharge.*

*This installation has been fitted on board under special survey. Tested under full working conditions and found satisfactory.
The workmanship was found to be good and sound.*

*It is submitted that
this vessel is eligible for
THE RECORD.*

Elec. Light.

W. J. 20/8/26

Total Capacity of Generators *7.5* Kilowatts

The amount of Fee ... £ *4 10 0* : When applied for, *29/6/26*

Travelling Expenses (if any) £ : : When received, *30/7/26*

Committee's Minute *GLASGOW 17 AUG 1926*

Assigned *Elec. Light.*

J. S. Rankin
Surveyor to Lloyd's Register of Shipping.



© 2019

Lloyd's Register
Foundation