

NAME *"Eleri" ex. "Desmona V"* Report No.

THICKNESSES OF PLATING ascertained by drilling, and comparison of same with the original thicknesses.

The thicknesses are in ~~of an inch~~ mm:

	AMIDSHIP.					FORWARD.					AFT.					REMARKS.
	Original Thickness.	Thickness by drilling.		Diminution if any.		Original Thickness.	Thickness by drilling.		Diminution if any.		Original Thickness.	Thickness by drilling.		Diminution if any.		
		Port.	Std.	Port.	Std.		Port.	Std.	Port.	Std.		Port.	Std.	Port.	Std.	
HAKE																
HAKE G	6	5.5	5.5	0.5	0.5											As the outside surface of the shell plating was entirely scaled to bare iron & the plating found, by internal and external examination, in good condition, and considering that the dry-dock was only available for a short time, the Owners' proposal to have the shell plating drilled forward & aft dispensed with, merits, in our opinion, the favourable consideration of the Committee.
F	4.5	4	4	0.5	0.5											
E	5	4.5	4.5	0.5	0.5											
D	4.5	4.5	4.5	✓	✓											
C	4.5	4	4	0.5	0.5											

No drilling made at ends

No drilling made at ends

Drillings at ends to be made in the vicinity of the peak bulkheads.

Foundation
W315-0193

as considered necessary, ...