



L. GARDNER & SONS, LTD, PATRICROFT, Nº MANCHESTER.	TYPE L3 CONES DESCRIPTION CONNECTING ROD FROM FORGING SCALE FULL SIZE	MATERIAL TO LLOYD'S INSPECTION AND TEST 83 STEEL NO 5005/204 40 CARBON STEEL (HEAT TREATED) ULTIMATE TENSILE STRENGTH ----- BETWEEN 40 & 30 TONS PER SQ IN YIELD POINT ----- NOT LESS THAN 25 TONS PER SQ IN ELONGATION PER CENT ----- NOT LESS THAN 20 REDUCTION OF AREA PER CENT ----- NOT LESS THAN 45 BRINELL HARDNESS NUMBER ----- BETWEEN 174 & 241 (455 1/4 & 310 1/4)	MATERIAL MACHINED ALL OVER PRINTS REC'D DATE 2.7.31	SUPERSEDES SUPERSEDED BY DRAWN BY J. R. TRACED BY CHECKED BY J. R.	DWG. Nº 1012H

Lily Maid IV

Don. rept. No. 15937.

MANCHESTER RPT 8303

L. Gardner & Son. Ltd

6 L3 Tyke engine for Yacht
LILY MAID IV

CONNECTING ROD



© 2020

Lloyd's Register
Foundation

W316-0204