

M.Y. "NARCISSUS".  
-----

Messrs. Camper & Nicholson & Co. Ltd.

Messrs. Sulzer Bros. Engines No. 5788 and 5794.  
-----

IT IS SUBMITTED with 2 S.C.S.A. Diesel Engines for main propelling purposes and having 6 cylinders 340 mm. diameter by 540 mm stroke, span of bearings 430 mm., maximum pressure in the cylinders 550 kg. per sq. cm., weight of flywheel 2400 kg., diameter of flywheel 1500 mm., and revolutions 220 per minute, the proposed sizes of shafting, viz:- crank 220 mm., and thrust 185 mm. diameter merit approval.

Return 2 plans (in duplicate).  
Retain copies.

*Ls/17/27*

*L.R.H.*

1.7.27.



© 2020

Lloyd's Register  
Foundation  
W316-0329