

1 / 1172 / 36

SCANTLING SECTION

TWIN SCREW MOTOR YACHT

TO CLASS LLOYD'S 100 A1 (YACHT RULES)

LLOYD'S NUMERALS

TRANSVERSE NUMERAL= 22

$$\frac{10.53}{22} \times 100 = 52.3\%$$

LONGITUDINAL NUMERAL = 2665.52

RATIO FACTOR = 1.0021

CORRECTED LONG² NO = 2671.12

SCALE:- $\frac{1}{2}'' = 1 \text{ FOOT}$

PRINCIPAL DIMENSIONS

LENGTH W.L.	118'-0"
BREADTH M ^{LD}	21'-0"
DEPTH M ^{LD}	11'-6"

EQUIPMENT NUMERICAL

LONGITUDINAL N°	2671.12
MAIN DECKHOUSE	$\frac{3}{8}(6783.716)$ 182.123
WHEEL HOUSE	40.218

EQUIPMENT NUMERAL 2893-46

1/1172/36

STEEL T.S.M.Y. N° 1172.

~~L. I. Thompson & Co. Ltd.~~
~~SCANTLING SECTION~~ (M. J. H. J. H. J. H.)
(M. J. H. J. H. J. H.)

Moh. Yacht Tadorna.

Sou. rept. No. 16791.

W319-0026



© 2019

Lloyd's Register
Foundation