

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

Enclosure.

12th November 1936.

Dear Sirs,

Messrs. Thornycroft's Ship No.1172

E.

I duly received your letter of the 5th instant, with enclosure advised therein, respecting the auxiliary set proposed by Messrs. L. Gardner & Sons Ltd. for the above vessel, and with regard thereto I have to inform you that with 4SCSA engines for driving auxiliary machinery, having 3 cylinders, 4.25" diameter by 6" stroke, span of bearings 5.1875", maximum pressure in cylinders 650 lb. per sq. inch, M.L.P. 108 lb. per sq. inch, B.H.P. 28.5, revs. per min.1000, the following size of crank shaft will be approved, viz:-

journals and pins..... 2.625" diameter.

Plan No.7318 showing details of crank shaft will also be approved and is returned herewith. I shall be glad if you will forward a verified copy of this plan, for reference purposes.

I am, Dear Sirs,

Yours faithfully,

The Surveyors,
MANCHESTER.



© 2019
Secretary.

Lloyd's Register
Foundation

W319-0061