

REPORT ON ELECTRICAL EQUIPMENT.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

5 MAY 1943

4 MAY 1943

Received at London Office

Date of writing Report.....19..... When handed in at Local Office.....19..... Port of HULL

No. in Survey held at Selby & Hull Date, First Survey 29. 12. 42. Last Survey 17. 4. 43.
Reg. Book. (Number of Visits.....1.....)

on the H.M.T. HERRING. Tons { Gross 357
Net 127

Built at Selby By whom built Cochran & Sons Ltd Yard No. 1260 When built 1943

Owners The Admiralty Port belonging to.....

Electrical Installation fitted by Wm Broady & Sons Ltd Contract No..... When fitted 1943

Is vessel fitted for carrying Petroleum in bulk no Is vessel equipped with D.F. Yes E.S.D. Yes Gy.C. no Sub.Sig. no

Have plans been submitted and approved Yes System of Distribution two wire Voltage of supply for Lighting 110

Heating 110 Power 110 Direct or Alternating Current, Lighting DB Power DB If Alternating Current state periodicity..... Prime Movers,

has the governing been tested and found as per Rule when full load is suddenly thrown on and off Yes Are turbine emergency governors fitted with a

trip switch as per Rule..... Generators, are they compound wound Yes, are they level compounded under working conditions Yes,

if not compound wound state distance between generators..... and from switchboard..... Where more than one generator is fitted are they

arranged to run in parallel....., are shunt field regulators provided Yes Is the compound winding connected to the negative or positive pole

negative Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing..... Have certificates of

test for machines under 100 kw. been supplied Admiralty Supply and the results found as per rule Yes Are the lubricating arrangements and the construction

of the generators as per rule Yes Position of Generators Engine room, starboard side

is the ventilation in way of generators satisfactory Yes are they clear of inflammable material Yes, if situated

near unprotected combustible material state distance from same horizontally..... and vertically....., are the generators protected from mechanical

injury and damage from water, steam and oil Yes, are the bedplates and frames earthed Yes and the prime movers and generators in metallic

contact Yes Switchboards, where are main switchboards placed Engine room starboard side near generator

are they in accessible positions, free from inflammable gases and acid fumes Yes, are they protected from mechanical injury and damage from water, steam

and oil Yes, if situated near unprotected combustible material state distance from same horizontally..... and vertically....., what insulation

material is used for the panels insulated with mica, if of synthetic insulating material is it an Approved Type....., if of

semi-insulating material (stone or marble) are all conducting parts insulated therefrom as per Rule..... Is the frame effectually earthed Yes

Is the construction as per Rule Yes including accessibility of parts Yes, absence of fuses on the back of the board Yes, individual fuses

to pilot and earth lamps, voltmeters, etc. Yes locking of screws and nuts Yes, labelling of apparatus and fuses Yes, fuses on the "dead"

side of switches Yes Description of Main Switchgear for each generator and arrangement of equaliser switches Double pole, quick

break knife switches & double pole fuses.

and for each outgoing circuit Double pole, quick break knife switches & double pole fuses

Are compartments containing switchboards composed of fire-resisting material or lined as per Rule Yes Instruments on main switchboard one

ammeters one voltmeters..... synchronising devices. For compound machines in parallel is the ammeter connected on the pole opposite to the

equaliser connection..... Earth Testing, state means provided Lamps connected to earth via switches & fuses

Switches, Circuit Breakers and Fuses, are they as per Rule Yes, are the fuses an approved type Yes, are all fuses labelled as

per Rule Yes If circuit breakers are provided for the generators, at what overload current did they open when tested....., are the reversed current

protection devices connected on the pole opposite to the equaliser connection....., have they been tested under working conditions, and at what current

did they operate..... Joint Boxes, Section Boards and Distribution Boards, is the construction and position as per Rule Yes

Cables, are they insulated and protected as per the appropriate Tables of the Rules Yes, if otherwise than as per Rule are they of an approved type.....

state maximum fall of pressure between bus bars and any point under maximum load 3V, are the ends of all cables having a sectional area of 0.04

square inch and above provided with soldering sockets Yes Are paper insulated and varnished cambric insulated cables sealed at the ends.....



with insulating compound or waterproof insulating tape. Are all the cable runs in accessible positions, not exposed to drip or accumulation of water or oil, high temperatures or risk of mechanical damage Yes, are cables laid under machines or floorplates no, if so, are they adequately protected no. Are cables in machinery spaces, galleys, laundries, etc., lead covered Yes or run in conduit no. State how the cables are supported and protected. Clipped to perforated steel trays or direct to steel or woodwork.
D.G. through bunker in added drum tube with glands & provision for drainage.
 Are all lead sheaths, armouring and conduits effectually bonded and earthed Yes. Refrigerated chambers, are the cables and fittings as per Rule no.
 Are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes, where unarmoured cables pass through beams, etc., are the holes effectually bushed Yes and with what material lead. Alternative Lighting, are the groups of lights in the engine and boiler rooms arranged as per Rule no. Emergency Supply, state position no and method of control no.
 Navigation Lamps, are they separately wired Yes controlled by separate double pole switches Yes and fuses Yes. Are the switches and fuses in a position accessible only to the officers on watch Yes, is an automatic indicator fitted no. Secondary Batteries, are they constructed and fitted as per Rule no, are they adequately ventilated no what is the battery capacity in ampere hours no.
 Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, weatherproof Yes. Are fittings installed where readily combustible materials or inflammable or explosive dust or gases are likely to be present Yes, if so, how are they protected Special admiralty fittings for engine & spirit rooms.
 and where are the controlling switches fitted mess deck above, are all fittings suitably ventilated Yes, are all fittings and accessories constructed and installed as per Rule Yes. Searchlight Lamps, No. of 2-10", whether fixed or portable portable, are their fittings as per Rule Yes. Heating and Cooking, is the general construction as per Rule Yes, are the frames effectually earthed Yes, are heaters in the accommodation of the convection type no. Motors, are all motors constructed and installed as per Rule Yes and placed in well-ventilated compartments in which inflammable gases cannot accumulate and free from damage from water, steam and oil Yes, if situated near unprotected combustible material state minimum distance from same horizontally no and vertically no. Are motors coupled to oil fuel transfer and unit pressure pumps capable of being stopped from a position accessible in the event of fire in the pump compartment no.
 Have motors of 100 BHP and over been inspected by the Surveyors during manufacture and testing no. Have certificates of test for motors under 100 BHP intended for essential services been supplied and the results found as per Rule Admiralty supply. Control Gear and Resistances, are they constructed and fitted as per Rule Yes. Lightning Conductors, where required are they fitted as per Rule no. Ships carrying Oil having a Flash Point less than 150° F. Have all the special requirements of the Rules for such ships been complied with no, are all fuses of the cartridge type no are they of an approved type no. Are the fittings for pump rooms, tween deck spaces, etc., in accordance with the special requirements for such ships no. Are the cables lead covered as per Rule no. Spare Gear, if the vessel is for open sea service have spares been provided as per Rule Yes, are they suitably stored in dry situations Yes. Insulation Tests, has the insulation resistance of all circuits and apparatus been tested and found satisfactory Yes.

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	1	15	115	130.5	875	Steam engine		
EMERGENCY								
ROTARY TRANSFORMER								

GENERATOR CABLES.

DESCRIPTION.	KILOWATTS.	CONDUCTORS.		MAXIMUM CURRENT IN AMPERES.		APPROX. LENGTH (lead plus return feet).	INSULATED WITH.	HOW PROTECTED.
		No. in Parallel Per Pole.	Sectional Area or No. and Dia. of Strands. Sq. ins. or sq. mm.	In the Circuit.	Rule.			
MAIN GENERATOR	15	1	37/072	130.5	152	20'	VIR	LC AP6154A
" EQUALISER						50'	"	"
Shore connection		1						
EMERGENCY GENERATOR								
ROTARY TRANSFORMER: MOTOR								
" GENERATOR								

MAIN DISTRIBUTION CABLES.

DESCRIPTION.	CONDUCTORS.		MAXIMUM CURRENT IN AMPERES.		APPROX. LENGTH (lead plus return feet).	INSULATED WITH.	HOW PROTECTED.
	No. in Parallel Per Pole.	Sectional Area or No. and Dia. of Strands. Sq. ins. or sq. mm.	In the Circuit.	Rule.			
AUX. SWITCHBOARDS AND SECTION BOARDS							
Engine room & after lighting	1	7/044	20	31	30'	VIR	LC AP6192A WE
Forward lighting	1	7/044	25	31	190'	"	"

LIGHTING AND HEATING, ETC., CABLES.

WIRELESS	1	7/036	15	24	200'	VIR	LC AP6193A WE
NAVIGATION LIGHTS	1	7/036	8	24	120'	"	"
LIGHTING AND HEATING							
Engine & boiler rooms	1	7/036	7	24	60'	"	"
Engine after lighting	1	7/036	10	24	50'	"	"
Engine lighting forward	1	7/036	5	24	90'	"	"
Officers	1	7/036	10	24	32'	"	"
Radiators	1	7/064	40	46	160'	"	AP6191A
10" searchlights	1	7/036	20	24	72'	"	6193A
Radio	1	7/044		31	220'	"	6192A

MOTOR CABLES.

ALL IMPORTANT MOTORS TO BE ENUMERATED.	No.	B.H.P.	CONDUCTORS.		MAXIMUM CURRENT IN AMPERES.		APPROX. LENGTH (lead plus return feet).	INSULATED WITH.	HOW PROTECTED.
			No. in Parallel Per Pole.	Sectional Area or No. and Dia. of Strands. Sq. ins. or sq. mm.	In the Circuit.	Rule.			
Ventilating fan 12 1/2"	1	1 1/2	1	7/029	14	15	60'	VIR	LC AP6194A WE
" " 7 1/2"	1	1/2	1	3/036	4.5	10	80'	"	6195A
" " 5"	4	1/2	1	3/036	2.5	10	90'	"	"
Domestic anti siphon 3 1/2"	2	1/2	1	3/036	5.2	10	90'	"	"

