

"WILLODALE"

268 x 38.33 x 19.67 Mtd.

Poop, R.Q., ~~to~~ Bridge and Forecastle: 63% superstructure
Machinery amidships Draught 17'-10" ext.

Built by R. Thompson & Sons, Sunderland in 1909

Owned by Bromage Shipping Co. Ltd. of Cardiff

Long holds forward of and abaft machinery space
subdivided athwartships by wood bulkheads *into 4 holds.*

Class: 100 A1

S.S. Npt. No. 1 - 36

Examined 7, 46 } *Nwr.*
Last docking 7, 46 }


In February, 1947, repairs were carried out to the
margin plate and a tank margin bracket in Nos. 1 and
2 holds on account of leakage, *from double bottom*

During a heavy storm on 4th April, 1947, a leak
developed in No. 2 hold. The ship listed and subsequently
sank. Water broke out of the hold and flooded the
engine room. *Vessel loaded with deck cargo of pit props*

There were 10 survivors.

*Summer 1947 2'-0 1/2"
causing danger of 17'-10"*

*S.R.
5.8.48*



© 2020

Lloyd's Register
Foundation

W322-0114