



Est. Rpt No 19413.

Comp + LMC & Alterations.

TSS "AVALON STAR"

Messrs Cammell Laird & Co Ltd. Birkenhead for re-cutting.

Port main gear wheel & pinions bearings remetalled.

Manoeuvring valve chest renewed. (report attached).

Port main feed pump shuttle valve renewed.

Bilge pump water end boxed out and bucket ring renewed.

Sole plate below steering engine, renewed.

Alterations.

The Port single ended boiler removed from the vessel and the starboard boiler with its seating, securely fitted amidships. The main & auxiliary steam & feed piping altered & part renewed, & water tested before fitting on board.

Marks on boiler left ashore.

N <sup>o</sup> 14055
LLOYDS TEST
350 LBS
WP 200 "
JSC 25-2-26

remarks

17055<sup>A</sup>

See cuts

attached

On the Port & star<sup>board</sup> sides of the Forward boiler, Oil fuel bunkers have been built, and N<sup>o</sup> 4 Deep tank Port & star<sup>board</sup>, has been altered to carry Oil fuel. The Filling & suction pipes with their controls have been fitted in accordance with the Rules & approved plans.

Electrical Installation.

In converting the vessel from Passenger to Cargo carrying, all the wiring & fittings in the passenger space have been taken ashore. All the new wiring for the Refrigerating machinery & Officers accommodation has been fitted in accordance with the Rules.

(List of Main cables attached) The installation was tried under power with satisfactory results.

N.B.—If this Report is copied by copying Press, especial care must be taken that the copying paper is not so much damped as to spread the ink, or to cause it to show through to the other side.

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THE MARGIN.



© 2020

Lloyd's Register  
Foundation