

LONDON

COPY.  
PORT OF GLASGOW

H

9th February, 1932.

Dear Sirs,

T.S.S. "AVELOMA STAR"

I have to acknowledge the receipt of your letter of the 6th instant regarding the stiffening of the bridge front in the above vessel and the contents have been noted.


With regard thereto I have to inform you that, as the protection afforded to the bridge front by the raised deck has been removed, all the bridge front stiffeners should be re-inforced by  $3\frac{1}{2} \times 3 \times .40$  reverse bars, the  $3\frac{1}{2}$  flange being fitted athwartship, and five rivet lugs should be fitted to the stiffeners top and bottom or other equivalent arrangements provided.

I am, Dear Sirs,

Yours faithfully,

The Surveyors,

GREENOCK.



Local Secretary.

Lloyd's Register  
Foundation

W334-0095