

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping,
Signal Letters (if any) L.G.D.R.

Official Number.		Name of Ship.		No., Date, and Port of Registry.			
161,818.		Benavon.		4 in 1930 Leith.			
No., Date, and Port of Previous Registry (if any). -----							
Whether British or Foreign Built.		Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.		Where Built.	When Built.	Name and Address of Builders.	
British		Steam Ship Single Screw.		Port Glasgow.	1930	Lithgows Limited Port Glasgow.	
Number of Decks		Two		Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post		Feet.	Tenths.
Number of Masts		Two				425	0
Rigged		Schooner		Length at quarter of depth from top of weather deck at side amidships to bottom of keel		425	8.5
Stern		Elliptical		Main breadth to outside of plank		56	0
Build		Clincher		Depth in hold from tonnage deck to ceiling at midships ...		29	0.5
Galleries		None		Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards		---	---
Head		None		Depth from top of beam amidships to top of keel		32	6.6
Framework and description of vessel		Steel Cargo		Depth from top of deck at side amidships to bottom of keel ...		31	7.2
Number of Bulkheads		(Five to Upp. Dk. One to 2nd Dk. Six in D.B. 1114)		Round of beam		1	1.7
Number of water ballast tanks, and their capacity in tons ...		Aft Peak - 1096 Deep Tank - 1096		Length of engine room, if any		61	3

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel } 12087 Tons. Ditto per inch immersion at same depth } 46.0 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Reciprocating, Steam Direct Acting, Vertical Triple Expansion.	Engines.	Engines.	Engines.	Three			576
		and	and	and	26"	51"	-----	2750
					43½"			
No. of Shafts.	Particulars of Boilers.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	S.E. Scotch Three Steel (ex tubes)	Boilers.	Boilers.	Boilers.	74"			11 Knots
	Number	British	1930	Rankin & Blackmore Ld., Greenock.				
	Iron or Steel							
	Loaded Pressure							

PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	5540.63	On account of space required for propelling power	1879.15
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	178.06
Turret or Trunk		These spaces are the following, viz.: Houses in Forecastle, and Bridge, and Houses on Bridge.	
Forecastle	55.35	(Number of Seamen or Apprentices for whom accommodation is certified)	
Bridge space	54.18		
Poop or Break			
Side Houses			
Deck Houses	155.86		
Chart House			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	16.19	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways	50.12	Masters Accommodation - 19.96	
		Chart Space - 3.90	
Gross Tonnage	5872.33	Wireless Telegraphy Space - 2.77	91.96
Deductions, as per Contra	2149.17	Boatswains Store - 58.72	
		Water Ballast Spaces - 6.61	
Register Tonnage	3723.16	Cubic Metres	
		16618.69	
		6082.15	
		10536.54	
		Total	2149.17

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 747.65 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 127.58 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Space in Forecastle	39.3 feet in length	- 13.22 tons.
" " " Bridge	121.2 " " "	- 337.25 "
" " " Poop	37.0 " " "	- 99.91 "

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
The Ben Line Steamers Limited) 28, Bernard Street, Leith,) Sixty-four (64) Shares. William Thomson of 28, Bernard St. Leith - Manager-.	
Dated 25th June 1930.	



Lloyd's Register
Foundation