

FREEBOARD PARTICULARS.

Name Thanchaco
 Class when below 100A
 Description of Vessel Shelter Deck
 Table A No. of page 53
 Moulded Depth 28 Feet 6 Inches.
 Coefficient of Fineness 77

Feet. Inches.

NORMAL FREEBOARD BY TABLES (WINTER)... 6 - 11 1/2

	Additions. Inches.	Deductions. Inches.
Sheer		6 1/2
Length... ..	3 3/4	
Erections		29 1/2
Height between Decks		
Round of Beam		
Iron Deck		3 1/2
Class being below 100A		
Statutory Deck Line	2	
Other Special Circumstances		
Summer Difference		6
TOTALS	5 3/4	45 1/2
Net Increase or Decrease		39 1/2
SUMMER FREEBOARD		3 - 8

W366-0011

cop... 32.76 ... 379.14 *