

TELEGRAMS:- "ISHERCON, FEN, LONDON"

180 Royal.  
TEL. NO. 1064 AVENUE.

V. ISHERWOOD,

SYSTEM OF SHIP CONSTRUCTION.

7 BATTERY PLACE, NEW YORK.

*1, Lloyd's Avenue,  
London, E.C. 3.*

RETAIN

PALMERS SHIPBUILDING & IRON CO., LTD.  
10,700 TON OIL TANKER (THE "BRACKETLESS-SYSTEM")

FREEBOARD PARTICULARS.

Class.....	100 A.1. + Lloyds.
Length between perpendiculars.....	430'-0"
Breadth moulded .....	57'-8"
Depth moulded to upper deck.....	34'-3"
Block coefficient extreme at load draft.	.795
Sheer ford. at perp: .....	8'-6"
" " " 1/8 L from perp:.....	4'-9"
" aft " perp:.....	4'-0"
" " " 1/8 L from perp:.....	2'-3"
Camber of beam at upper deck .....	14"
Tumble home at upper deck.....	7"
Upper deck.....	unsheathed
Poop.....	Length 102'-8" Height 7'-6"
Bridge.....	" 28'-3" " 7'-9"
Forecastle .....	" 42'-6" " 7'-6"



© 2020

Lloyd's Register  
Foundation

W346-0018