

MIDSHIP SECTION.

N^os 408 & 9 S.Ss

SCALE: $\frac{1}{2}$ " = 1 FOOT.

TO CLASS 100.A1, AT LLOYDS.

1921-2. RULES

DIMENSIONS:
419.3' x 54.29' = 32.58 MLD TO UPPER DK.

<u>NUMERALS</u>		
BREADTH	=	54.29
DEPTH	=	32.58
TRANSVERSE No.		86.87

LONGITUDINAL N° = 36,424

$\alpha = 18.0$

PROPORTIONS

DEPTHS TO UPPER D ^K	12.87
" " BRIDGE D ^K	10.34

EQUIPMENT NUMBER.

(54.29 + 32.58) × 419.3	=	36424
POOP 37.00		
BRIDGE 138.50	} 220.25 × 7.95 × 75 =	1313.24
FCLE 44.75		
HOUSES 62 × 7.5 × .5		232.50
HOUSE 31' × 8 × .5		124.00
CASINGS 44.5 × 7.5 × .5		166.90
		38260.64

3 BOWER ANCHORS	64½ CENTS. STOCKLESS
1 STREAM ANCHOR	19 " EX. STOCK
270 FATHOMS	2 7/8 STD CHAIN CABLE
90 "	5 " STREAM STEEL WIRE
120 "	5 1/4 TOWLINE " "
2 @ 90 "	2 3/4 HAWSER " "
1 @ 90 "	2 1/2 WARP " "
1 @ 90 "	7 " MANILLA WARE

SHEERSTRAKE 57 * 92 TO 46.
 64 IN BRIDGE + 02 * 66. DOUBLED
 FOR 20' 3" AT ENDS OF BRIDGE.
 BUTTS QUINTEUPLE SPACED FOR 1/2 L.
 OUTSIDE BRIDGE AS PER THICKNESS.

56' x .74 TO .46.
 .64 IN BRIDGE + .02 = .66
 BUTTS LAPPED & QUADRUPLE RIVETED
 FOR 1/2 LENGTH OUTSIDE BRIDGE.

See above.

BULGE KEEL 6" x 4" x .46 TEE }
BULB PLATE 11" x 9/20 }

Diagram illustrating the floor plan of a building section, showing three circular rooms arranged horizontally.

- Rooms:** Three identical circular rooms, each with a diameter of 10'-4".
- Frames:** The spaces between the rooms are labeled "FRAMES 7'-3" BA."
- Outer Walls:** The exterior walls are labeled "Rev 4'-3 1/2"
- Floor:** A dashed line indicates the "FLOOR" level.
- Dimensions:**
 - The overall width of the section is 3 3/4" x 3 3/4".
 - The depth of the rooms is 7' x 3' - 48A.
 - The distance from the center of a room to the adjacent wall is 3 3/4" x 3 3/4".

ELEVATION OF INTERCOSTALS.

Approved for h0 412
2/8/27

APPROVED
LLOYDS REGISTER OF SHIPPING

APPROVED *for AIO*
LLOYDS REGISTER OF SHIPPING

(1921-2 Rules)
Midship Section

Nos 408/9 & 410 & 412.
C Connell & Co

408 PLANTER *

Glasgow Rpt. 47211

409 RANCHER

Glas. Rpt. 47462

410 Freeboard
GLASGOW/REPORT No 47591

Blower

GLASGOW REPORT No 47644

412. "CUSTODIAN"

GLASGOW REPORT No. 48174



© 2020

Lloyd's Register
Foundation

W350-0102