



OWNERS EXTRA SCANTLING
THE FOLLOWING EXTRAS IN EXCESS OF LLOYDS' REQUIREMENTS
HAVE BEEN ADDED IN AGREEMENT WITH OWNERS.
UPPER DECK INCLUDING STRINGER .10 INCREASE THROUGHOUT
EXCEPT STRAKE ADJACENT TO CENTRE STRAKE, INCREASE ON WHICH IS .04 THROUGHOUT
SHEERSTRAKE .10 INCREASE FOR 5/8 LEN. AMIDSHIPS
STRAKE BELOW SHEERSTRAKE .05 FOR 5/8 LEN. "
STRAKE BELOW MAIN DK. " " " " "

2539
J.H.
2/9/21

BRIDGE SIDE PLATING CARRIED DOWN TO
DECK AT BRIDGE ENDS INCREASED TO .48 FOR WIDE FR. SPACING
SHEERSTRAKE 1.08 AT BRIDGE ENDS
BRIDGE SIDE PLATING AT BRIDGE ENDS .50 + .04 FOR WIDE FR. SPACING.

FORECASTLE FRONT .36" CORNING 18" x 36"
STIFFERS 3/8" x 3" x 46" B.D. SPACED 36" APART

POOP FRONT PLATING .46" CORNING 18" x 36"
STIFFERS 3/8" x 3" x 46" B.D. SPACED 36" APART
BRACKETED TOP & BOTTOM
7 1/2" x 58 1/2" @ 36"
7 1/2" x 58 1/2" @ 33"

BRIDGE END PLATING .32" CORNING 18" x 36"
STIFFERS 3/8" x 3" x 46" B.D. SPACED 36" APART

FRAME SPACING IN BRIDGE TWIN DECKS
8'1" AT BRIDGE ENDS TO 8'9" AT CENTRE

BRIDGE FRONT PLATING .46" CORNING 18" x 36"
STIFFERS 3/8" x 3" x 46" B.D. SPACED 36" APART
BRACKETED TOP & BOTTOM

FORECASTLE FRONT .36" CORNING 18" x 36"
STIFFERS 3/8" x 3" x 46" B.D. SPACED 36" APART

— PROFILE AND DECKS. —
DIMENSIONS — 440'-0" B.P. x 56'-9" M.D. x 33'-11" M.D. TO UPPER DECK.
SCALE 1/8" = 1 FT.

BRIDGE DECK

BRIDGE END	BRIDGE FRONT
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42

for Bridge front, Poop front,
& side only.

PART PROFILE PLAN

CALEDON S. B. & E. Co. LTD,

S. S. No. 282/3

Sl. 282 = "British Commander"

Sl. 283 = "British Commodore"

DUN. RPTS. No. 8400 & 8423.

3/

Week Section

458

RETAIN

RETAIN

W351 - 0070



© 2021

Lloyd's Register
Foundation