

Recd 26/10/11

Copy

I the Undersigned Surveyor to Lloyds Agency & Surveyor to Lloyds Register of British & Foreign Shipping do &c &c, do hereby Certify that, at the request of Captain Catoe of the Barque "Magnolia," I this day attended on board the said vessel, lying in the Caledonian dry Dock, at Howrah, to ascertain what repairs had been effected, in order to be enabled to report on the ship, & after carefully ascertaining the extent of the said repairs, I now report as follows, that is to say:

The Barque "Magnolia," of 1083 tons, was built at St John N.B. in the year 1855, of mixed timber - she is now classed D.F. in Lloyds Register of B. and F. shipping, also holds the class 5/6. A. 1. in the Veritas Register & has an American Certificate as well.

This vessel was originally a strong built ship of her class & as she has just undergone the underneath mentioned repairs, I consider her a Good Insurance Risk -.

Repairs lately effected to the Magnolia in the Caledonian Dock.

Ship stripped cleaned down & painted throughout including all decks.

Hanging knees refastened with 350 New Iron Bolts. The Butts of the topside planking have been rebarked when necessary.

Two new iron hanging knees have been supplied & fitted between deck & one No. Open lower hold.

Four new staple iron knees have been fitted between decks, abreast of the fore & main masts.

The ship has been newly sheathed from the hull
to the lower part of the boot topping with $\frac{1}{2}$ " teak
plankeas.

The scuppers have been repaired when necessary, & the
piping has been remated over ordinary felt with 16, 18,
20 oz. heavy metal.

M. Stewart R.N.R.

Calcutta

The 2nd September } Registered in this Agency dated in Calcutta 2nd Sept^r
1875 }

87703.

(Copy)

Gladstone Wylie & Co.

— Yents to Lloyds —

