

G.R.130.


GLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping. Signal Letters (if any)

Official Number.	Name of Ship.	No., Date, and Port of Registry.	
167074	CAPE FINISTERRE	65/1939	HULL.



No., Date, and Port of Previous Registry (if any).				
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Single Screw	Selby	1939	Cochrane and Sons Ltd. Selby.
Number of Decks	One & raised Quarter deck.	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet. 178	Tenths. 2.5
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	30	1.5
Rigged	Ketch	Depth in hold from tonnage deck to ceiling at midships	15.	3
Stern	Cruiser.	Depth in hold from upper deck to ceiling at midships in the case of three decks and upwards		
Build	Cléncher	Depth from top of beam amidships to top of keel		
Galleries	Stem Raked.	Depth from top of deck at side amidships to bottom of keel		
Head		Round of beam		7.5
Framework and description of vessel	Steel Trawler Four watertight	Length of engine room, if any	37	5
Number of Bulkheads	One Non watertight			
Number of water ballast tanks, and their capacity in tons	None			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel	Tons.	Ditto per inch immersion at same depth	Tons.
--	-------	--	-------

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Triple Expansion direct acting Inverted Cylinder	British	1939	Charles D. Holmes & Co. Ltd. Hull.	Three 14 1/2"	27"		163 870 1000
one	Particulars of Boilers. Cylindrical Multitubular. Number One. Iron or Steel. Steel. Loaded Pressure 225 lbs	British	1939	Charles D. Holmes & Co. Ltd. Hull	24 1/2" 41"			13 Knots

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck		507. 00	On account of space required for propelling power		260. 86
Space or spaces between Decks		4. 30	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		75. 36
Turret or Trunk			These spaces are the following, viz. :- Under Forecastle on Raised Quarter Deck Below deck forward. Below Deck aft. (Number of Seamen or Apprentices for whom accommodation is certified 25.)		
Forecastle (Side Houses under.)		4. 30	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-		
Bridge space			Master's Accomodation. 12.88)		
Pop or Break		26. 07	Chart Space. 2.44)		
Side Houses			Wireless Telegraphy 4.38)		
Deck Houses		33. 41	Boatswain's Store 10.00)		
Chart House			Total ... ..		29.70
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		19.99			
Excess of Hatchways					
Gross Tonnage		590. 77			
Deductions, as per Contra		365. 92			
Register Tonnage		224. 85			365. 92

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 129.07 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 30.57 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open space under Forecastle, Length 30.15 feet - 22.07 Tons.

Name of Master	Certificate of	Service No.	Competency No.
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.			
Hudson Steam Fishing Company Ltd. having its principal place of business @ St. Andrews Dock. in the City and County of Kingston-upon-Hull.			
Archibald Hudson. of 44 Davenport Avenue. Hessle. E. Yorks.			
Sixty four (64) shares. designated the person to whom the management of the vessel is entrusted by and on behalf of the owners. Advice received the 19th day of Oct. 1939 under the hand of Stanley James Waltham, Public Officer to Hudson Steam Fishing Co. Ltd.			
Dated 19th October, 1939			

