

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey Hull
Date of Survey 31st Jan. 1933
Name of Surveyor

Ship's Name. **CONTINENTAL COASTER**
Port of Registry and Nationality. London
Official Number. 124058
Gross Tonnage. 531
Date of Build. 1907.3
Particulars of Classification. + 100 A1

Number in Register Book

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	164.8	26.6	11.0	378.60
Length on LOADLINE.	164.8	Frame Depth $\frac{25}{25}$ Rule	Ceiling Sheer $\frac{26}{26}$	Peak Tanks 11 10
			Depth $\frac{12.66}{12.66}$	
CORRECTED DIMENSIONS.	164.8	26.6	12.92	399.60

Moulded Depth as measured..... 13' 4"

Addition for Keel below base line for draught record.....inches.

NOTE.— If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH.

Length of Ship on Loadline..... 164.8
Length in Table 160.0
Difference 4.8
Correction for 10ft., Table A.9 Table C.
× Difference divided by 10 432 (if required.)
If $\frac{1}{10}$ ths length covered divide by 2 231 = + $\frac{1}{4}$

CORRECTION FOR IRON DECK.

Proportion covered, if less than $\frac{1}{10}$ ths length covered
Thickness of usual wood deck, less stringer 3 -3

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships..... 26.0
Round of Beam $\frac{6}{2}$
Normal round..... $\frac{6}{2}$
Difference $\div 2 =$
Proportion of Deck uncovered (Para. 19) ✓

NOTE.— The round of beam should be reported on the full breadth of vessel at the gunwale.

Co-efficient of fineness..... 70

Any modification necessary }
[Para. 4 (a) to (e)]*

Co-efficient as corrected 70

Sheer { Stem..... 42 } $71\frac{3}{4} \div 2 = 35.87$...Mean
at { Sternpost ... 29 } $\frac{3}{4}$

Sheer at $\frac{1}{2}$ of the length from { Stem 23 } $42\frac{3}{4} \div 2 = 21.37$...Mean
Sternpost 19 } $\frac{1}{2}$

Gradual mean Sheer 35.87
Standard mean Sheer [Table, Para. 18] 26.48 Correction
Difference..... $\frac{9.39}{4} = - 2\frac{1}{4}$
If limited as Para. 18 (f)

Rise in Sheer { At front of bridge house.....
from amidships { Para. 18 (e) } At after end of forecastle ✓

Fall in Sheer } $\div 2 =$
Para. 18 (d) }
Length uncovered Correction ✓

ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C..... $4\frac{1}{4}$
Correction for Length, if required (Para. 12, 13, and 14)
Freeboard by Table A, corrected for sheer, and for length, } $1 - 9\frac{3}{4}$
if required (Para. 11, 12, 13, and 14) }
Difference $1 - 5\frac{1}{2}$
Percentage as below..... 56.95
Correction for R. Q. Dk. if engine and boiler openings not } $- 10$
covered by bridge house (Para. 11) } $+ \frac{1}{4}$
Allowance for Deck Erections $- 9\frac{3}{4}$

	Length.	Length allowed.	Height.
Forecastle.....	21.0	20.8	6.4
Bridge House.....	10.5	10.5	7.0
Raised Qr. Dk.....	86.3	86.3	4.04
Top.....			
Total		$\frac{117.6}{164.8} = .713$	
Length of Ship			
Corresponding percentage } 56.95 (Para. 11, 12, 13, or 14)			

Freeboard, Table A 2.0
Correction for Sheer $- 2\frac{1}{4}$
Correction for Length $+ \frac{1}{4}$
Allowance for Deck Erections $- 9\frac{3}{4}$
Correction for Round of Beam..... $1 - 0\frac{1}{4}$
Correction for fall in Sheer (if any).....
Correction for Steel Deck (if required) $- 3$
Additions for non-compliance with provisions of } $9\frac{1}{4}$
Para. 11 (d) and (e) }
Other Corrections (if any)

Winter Freeboard 0. $9\frac{1}{4}$
Summer Freeboard 0. $7\frac{3}{4}$
Indian Summer Freeboard
N. A. Winter Freeboard

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side.

Winter Freeboard from deck line
Summer " " " "
Indian Summer " " " "
N. A. Winter " " " "

Raised Quarter

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:—

Tropical Fresh Water Line above Centre of Disc ...	5	Tropical Fresh Water Freeboard ...	4.3
Fresh Water Line " " ...	$3\frac{1}{2}$	Fresh Water " " ...	4.4
Tropical Line " " ...	$1\frac{1}{2}$	Tropical " " ...	4.6
Winter Line below " " ...	$1\frac{1}{2}$	Winter " " ...	4.9
Winter North Atlantic Line " " ...	$4\frac{3}{4}$	Winter North Atlantic " " ...	5.0

6 FEB 1933

215,932. T.

1212
4488.7

W377-0149

8 MAR 1933

FOUR 120 FEB 1933

RECEIVED