

COPY.

Lloyd's Register of Shipping.

No. 1126

Port of **BATAVIA.**

the 12th of June 1933.

This is to Certify that

the undersigned Surveyor to this Society did at the request of

Mrs. MacLaine Watson, Lloyd's Agents at this port, hold a survey on the British steel screw steamer "CLAN MACNAB", 6117 tons gross Glasgow, No. 60152 of the Register 1932/33, in order to ascertain nature and extent of damage sustained to the intermediated conical shaft between the turbine and tunnel shafting and report as follows:


FIND: The conical shaft, being hollow, that connects the main engine and the turbine with the tunnel shafting had a crack through and through from the big flange to a bolthole in the big flange, just on top of the keyhole.

Recommendation. Being there no more space, a shrinkring to be fitted around the big flange of the conical hollow shaft, 3" by 3". Shrinkrings to be fitted around the small flange each of 4"x2 1/2". Shrinkrings to be cut from thick plates. Bolt clamps to be fitted between the flanges and bolt-studs, each 4" by 4" and fitted with bolts of 3". Bolt clamps to be cut and afterwards lathed from pieces of iron not forged. The boltclamps to be fitted close to each other and the most wearing against the bolts of the small and hindmost flange, so preventing slackening by removing of the clamps in the direction of the most flange.

This work was carried out satisfactorily and the ship is fit to proceed on her voyage to Great Britain and having permanent repairs.

A copy of this report has been sent to Lloyds Register of Shipping, London.

F 200.00
F 50.00
F 250.00



at Batavia on the 12th of June 1933.

P. MacLaine, Watson

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—
The Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other of the Society, or for any error of judgment, default, or negligence of the Committee or any Member thereof, or of any Officers or Agents of the Society."