

Rpt. C 12(a).

FREEBOARD VERIFICATION FORM FOR ORDINARY CARGO ~~AND~~ ^{OR} ~~PASSENGER~~ SHIPS.

When received in London Office

Port GLASGOWName "CLAN MACNAB"Official No. 144229No. in Reg. Book 17963Port of Registry (For Foreign Ships) GlasgowIron or Steel STEEL State whether Classed by Lloyd's Register YESName of Owners THE CLAN LINE STEAMERS CO. Date of Verification 1st MAY 1932

I have to report that the Freeboards as given below, assigned by the Committee to this ship, have been correctly marked on the ship's sides, in accordance with the printed instructions:—

| FREEBOARD AMIDSHIPS FROM TOP OF DECK LINE, WOOD /STEEL DECK. | | FROM CENTRE OF DISC. | |
|--|-------------------|----------------------|--|
| Tropical Fresh Water | 7 ft. 3 3/4 ins. | 14 1/2 ins. above | |
| Fresh Water | 7 ft. 10 3/4 ins. | 7 1/2 ins. above | |
| Tropical | 7 ft. 11 1/4 ins. | 7 ins. above | |
| Summer | 8 ft. 6 1/2 ins. | | |
| Winter | 9 ft. 1 1/4 ins. | 7 ins. below | |
| Winter North Atlantic | 7 ft. ins. | ins. below | |

Maximum Summer Draught corresponding to the freeboard assigned as shown on the Builders' Displacement Scales:—

(OVER)

H. Munro. Surveyor.

(To be filled up in London Office.)

Statement No. 29442 Date of Committee's Minute 2-5-32

Particulars for Record in Register Book.

| | | |
|-----------------------|--------|------------|
| Moulded Depth | 36 ft. | 0 ins. |
| Freeboard | 8 ft. | 6 1/4 ins. |
| Corresponding Draught | 27 ft. | 9 ins. |

Freeboards compared and found correct by S.W.B. Date 11-5-32

Is fee paid?

Form for Certificate L.L. 2

Instructions

Date

Certificate written 11/5/32Noted for posting 11/5/32

1. The Ventilator openings 10'-5" in height have been specially supported.
2. Two air pipes amidships 12" in height have been fitted with ball valves
3. The gauge closing appliances to the air pipes have been removed
where in bad condition.
4. Ladders have been provided on the foreboard deck for the protection
of the crew.

Pa

Appliance

ecastle ...

dge, Fore end

dge, After end

ised Quarter Deck

op ...

0m.3.32.



© 2019

Lloyd's Register
Foundation