

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.

PARTICULARS IN RESPECT OF STEAM SHIPS HAVING ~~SEAR OR~~ ^{Shelter} AWNING DECKS.

Port of Survey

Date of Survey **15. 4. 32**

Name of Surveyor

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
S/S DAVISIAN	Liverpool British	147200	6433.39	1923	+100 A1 Shelter Deck with freeboard
Number in Register Book					

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK Tonnage.
	400.35	52.5	26.95 00	4542.83 U.D. 1508.18 STD
Length on LOADLINE	399.5	Frame Depth 9 Rule " 6 x 2/3 - 50	Ceiling +.20 Sheer +.50 Fall in Tank +.16	Peak Tanks
CORRECTED DIMENSIONS.	399.5	52.00	27.81	4542.83

Co-efficient of fineness **.786**
 Any modification necessary [Para. 4 (a) to (e)*] } **Cell. D. B.**
 Co-efficient as corrected **.77.**

Allowance for strength in excess of Lloyd's rules = **37" (Table A Limit)**

State particulars—

3 Complete steel decks. Deep built angle frames.
7 W.T. bulkheads to shelter decks
11/12 Bulk bulkheads to upper deck.
2 W.T. bulkheads to 2nd decks.

No tonnage opening.

Sheer at Stem **90** at 1/2 length from Stem **50.75**
 Sternpost... **46.75** " " " Sternpost... **24.25**
 Drop in Sheer abaft amidships.....

Shelter
 Round of Spar-deck Beam..... **13**
 " " Main-deck " **13**

	Length	x	Height.	State if open or closed at ends.
Forecastle		x		
Bridge.....	143	x	8'-0"	closed forward open aft.
Poop		x		

Moulded Depth as measured **29-6** upper Main Deck.
 " " " **37-7 1/2** Shelter Spar or Awning Deck.

Addition for Keel below base line for draught record..... **2 3/4** inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH:—

Length of Ship on Load Line.... **399.5**
 Length in Table **354.0**
 Difference..... **45.5**
 Correction for 10ft..... **.80**
 x Difference ÷ 10 = **+ 3 3/4**

Height of 'Tween Decks..... **8'-1 1/2"**
 (From top of beam to top of beam at side)
 Correction for Height of 'Tween Decks in Spar-decked Ships.....

Freeboard Table B or C	4'-2 1/4"
Correction for Length.....	3 3/4
	4'-6
Correction for Height of 'Tween Decks in Spar-decked Ships.....	8'-1 1/2
	12'-7 1/2

Correction for Strength in excess of Lloyd's rules..... **3-1**
9-6 1/2

Correction for Iron Deck if required..... **- 3 1/2**
9-3

Other Corrections (if any).....

Winter Freeboard.....	9-3
Summer Freeboard.....	8-8 1/2
Indian Summer Freeboard.....	8-2
N.A. Winter Freeboard.....	✓

Correction necessary because clearside amidships measured in accordance with the Statute is not taken at intersection of the wood or steel deck with side

Winter Freeboard from Deck Line	
Summer " " "	
Indian Summer " " "	
N.A. Winter " " "	

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:—

Tropical Fresh Water Line above Centre of Disc ...	14 1/4	Tropical Fresh Water Freeboard ...	8'-8 1/4"
Fresh Water Line " " " ...	7 3/4	Fresh Water " " " ...	7'-6"
Tropical Line " " " ...	6 1/2	Tropical " " " ...	8'-0 1/2"
Winter Line below " " " ...	6 1/2	Winter " " " ...	8'-1 3/4"
Winter North Atlantic Line " " " ...	✓	Winter North Atlantic " " " ...	9'-2 3/4"

APR 1932

1m 2.32.

W381-0160

MARKING FORM
 17 OCT 1936
 RECEIVED

MARKING FORM
 Lloyd's Register
 Foundation