

c.131.

REEBOARD REPORT on the

S/S RAY LIGHT.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, Subject to

- (1) The air pipes on the upper deck & also the air pipe on the raised quarter deck to the after peak having a snifting hole drilled in the upper part of the bend. Also efficient means being provided for closing the openings of all air pipes.
- (2) Gangways, lifelines, & other satisfactory means for the protection of the crew being provided in the forward well.
- (3) The freeing port area in the Raised Quarter Deck Bulwarks being increased to 202 sq. ft. on each side of the ship.

RETAINED

Iss to Gls Owners 7/4

Convention.

W382-0116



© 2021

Lloyd's Register
Foundation

S.P.B.

4.5.32
1. 4. 32

Name of Broker or Agent