

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey

Date of Survey

6.6.32

Name of Surveyor

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
DEMETERTON.	Newcastle British	149406	5251	1926/2.	+100A1-
Number in Register Book					

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	397.25	54.0	28.6	4791.55
Length on LOADLINE.	397.25	Frame Depth 14.2 Rule " 7 7.5 x 2 = 15 Shore ceiling fitted.	Ceiling 14.2 Sheer +1.16	Peak Tanks 7 web. 2.0 rise in aft 32.50
CORRECTED DIMENSIONS.	397.25	58.75	29.76	4824.05

Co-efficient of fineness..... **.774**
Any modification necessary }
[Para. 4 (a) to (e)]* } **.020**
Co-efficient as corrected **.75**

Sheer { Stem..... **120**
at { Sternpost ... **66** } $186 \div 2 = 93$... Mean
Sheer at $\frac{1}{8}$ of the length from { Stem **67.5**
Sternpost **33.5** } $101 \div 2 = 50.5$... Mean
Gradual mean Sheer **91.81** $\div .55 = 91.81$
Standard mean Sheer [Table, Para. 18] **49.72** Correction
Difference..... **42.09** $\div 4 = 10.52$
If limited as Para. 18 (f) **-10.5**

Rise in Sheer { At front of bridge house.....
from amidships {
[Para. 18 (e)] { At after end of forecastle ☒

Fall in Sheer }
Para. 18 (d) } $\div 2 =$
Length uncovered ☒ Correction

ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C..... **4.11 1/2**
Correction for Length, if required (Para. 12, 13, and 14) **+ 1 1/2**
Freeboard by Table A, corrected for sheer, and for length, if required (Para. 12, 13, and 14) } **5.1**
Difference **7.5 1/2**
Percentage as below..... **30.53** **2.44 1/2**
- 8 3/4

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11) }

Allowance for Deck Erections **- 8 3/4**

	Length.	Length allowed.	Height.
Forecastle.....	38.6" + wing	39.5	8.0"
Bridge House.....	121.9" + wing	118.5	8.0"
† Raised Qr. Dk.....			
Poop.....	32.3	32.25	8.0"
Total		190.25	.479
Length of Ship	397.25		
Corresponding percentage { (Para. 11, 12, 13, or 14) } 30.55 ✓			

Moulded Depth as measured..... **31.6"**

Addition for Keel below base line
for draught record..... inches.

CORRECTION FOR LENGTH.

Length of Ship on Loadline..... **397.25**
Length in Table **378.00**
Difference **19.25**
Correction for 10ft., Table A. **1.6** Table C. **.8**
× Difference divided by 10 **3.08** (if required.) **1.84**
If $\frac{1}{10}$ ths length covered divide by 2 **+3** **1 1/2**

CORRECTION FOR IRON DECK.

Proportion covered, if less than $\frac{1}{10}$ ths length covered **.4799**
Thickness of usual wood deck, less stringer **3 1/2** **1 3/4**

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships..... **53.2"**
Round of Beam **1.1 1/2**
Normal round..... **1.1 1/4**
Difference $\frac{1}{4} \div 2 =$ **1/8**
Proportion of Deck uncovered (Para. 19)

Freeboard, Table A **8.1**
Correction for Sheer **10 1/2**
Correction for Length **7.2 1/2**
Allowance for Deck Erections **3**
Correction for Round of Beam..... **7.5 1/2**
Correction for fall in Sheer (if any)..... **83/4**
Correction for Steel Deck (if required) **6.8 3/4**
Additions for non-compliance with provisions of }
Para. 11 (d) and (e) † } **- 1 3/4**
Other Corrections (if any) **6.7**

Winter Freeboard **6.7**
Summer Freeboard **5 3/4**
Indian Summer Freeboard **6.1 1/4**
N. A. Winter Freeboard **5.7 1/2**

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side.

Winter Freeboard from deck line
Summer " " " "
Indian Summer " " " "
N. A. Winter " " " "

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:—

Tropical Fresh Water Line above Centre of Disc ...	13.	Tropical Fresh Water Freeboard ...	5.0 1/2
Fresh Water Line " " " " ...	7.	Fresh Water " " " " ...	5.6 1/4
Tropical Line " " " " ...	6.	Tropical " " " " ...	5.7 1/4
Winter Line below " " " " ...	5 1/2	Winter " " " " ...	6.6 3/4
Winter North Atlantic Line " " " " ...	✓	Winter North Atlantic " " " " ...	

7 JUN 1932

W383-0192

RECEIVED

RECEIVED 30 APR 1934

RECEIVED