

Co-offici
Any mo
[Par

"O.A. KNUDSEN" - No. 10.

Freeboard Particulars.

forward at stem 10'5"
aft at stern post 5'3"
1/8 length from stem 5'8⁵/₄"
1/8 length from sternpost 2'10-5/8"
of beam Upper deck 15¹/₂"
between perpendiculars on I.W.L. 469'3"
of poop 93'6"
of Bridge Dk. 32'6"
of Forecastle 40'0"
astered dimensions 470.0' x 62.2' x 35.3'
er deck tonnage 8268.61
th of keel below base line 3'8"

go hatch forward 15'9" long x 12'0" broad

Side coaming 2'9" x .44"

Two webs each 11" deep at cr.

Top and bottom angles on webs 3" x 3" x .40" double

edge front bulkhead.

Plating .40

Coaming .44

Stiffeners 9" x 3" x .46 spaced 2'3" to 2'6" (lugged top and bottom)

W.T. door on bridge front

idge rear tonnage openings 5'0" x 3'0" - 2 off - Opening 18" above deck.

recastle front tonnage openings - 2 off - 4'6" x 4'0" - 18" coamings

op front has W.T. door.

Lowest point of deck



© 2019

Lloyd's Register

Particulars supplied by the Norwegian Ship Control (Tonnage Dept.)

W285-0052